


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pratt County. Sec. 23 Twp. 26S Rge. 14 (X) (W)
Location as "NE/CNW/SW" or footage from lines SE/4 NE/4 SE/4
Lease Owner Dunne-Gardner Drilling Co., Inc.
Lease Name Ohley Well No. 1
Office Address 300 Schweiter Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed May 28, 1963
Application for plugging filed May 28, 1963
Application for plugging approved 1963
Plugging commenced May 28, 1963
Plugging completed May 28, 1963
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation Depth to top Bottom Total Depth of Well 4559 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe		-0-	598'	8-5/8"	5-15-63	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 240' from surface; set plug, 1/4 sack hulls and 20 sacks of cement; filled surface pipe with heavy mud to 40' from surface; set plug, 1/4 sack hulls and 10 sacks of cement.
Filled rat hole with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 29 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
Address

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Don Gardner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
300 Schweiter Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of May, 1963

My commission expires November 9, 1965

[Signature]
Marilyn E. Fox
Notary Public.

INVOICED

DATE 5/29/63
INV. NO. 7191-12

DRILLER'S LOG

OPERATOR: Dunne-Gardner Drilling Co., Inc.
300 Schweiter Building, Wichita 2, Kansas

LEASE: OHLEY

WELL: No. 1

LOCATION: SE NE SE Sec. 23-26S-14W
Pratt County, Kansas

CONTRACTOR: Dunne-Gardner Drilling Co., Inc.

DATE COMMENCED: May 14, 1963

DATE COMPLETED: May 28, 1963

TOTAL DEPTH: 4559'

CASING: Set 8-5/8" surface pipe @ 598' with 600 sacks cement

<u>FROM</u>	<u>TO</u>	
0	165	Sand
165	396	Blue Shale and Red Bed
396	876	Red Bed
876	891	Anhydrite - Lime
891	1315	Red Bed, Shale and Shells
1315	1870	Shale - Lime Streaks
1870	2715	Shale and Lime
2715	2864	Shale
2864	3249	Lime and Shale
3249	3435	Lime
3435	3546	Lime and Shale
3546	4287	Lime
4287	4325	Chert
4325	4472	Chert and Lime
4472	4525	Lime, Sand and Shale
4525	4559	Lime and Shale
4559		Total Depth

RECEIVED
STATE CORPORATION COMMISSION

JUN 10 1963

I certify the above to be true and correct to the best of my knowledge and belief.


DUNNE-GARDNER DRILLING CO., INC.

By


Don Gardner

Subscribed and sworn to before me this 4th day of June, 1963.

My Commission Expires:
November 9, 1965


Marilyn E. Fox, Notary Public