

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-151-22183-0000
LEASE NAME Berry
WELL NUMBER No. 1

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

330 Ft. from South Line of Section
1650 Ft. from East Line of Section

LEASE OPERATOR National Petroleum Reserves, Inc. SPOT LOCATION Se Sw Se
ADDRESS 250 N. Rock Rd, #130 Section 23 Township 26s Range 14w
CITY, STATE, ZIP Wichita, Kansas 67206 County Pratt
PHONE # 316-681-3515 Date Well Completed February 14, 200
Character of Well Dry and Abandoned Date Plugging Commenced February 14, 200
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed February 14, 200

The plugging proposal was approved on February 13, 2001 at 8:45 am (date)
by Steve Durrant (KCC District Agent's Name)
Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 4550

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	168	and		
Redbeds	Shale	168	310	8-5/8"	295.12	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged well as follows using 135 sx 60/40 Poz, 6% Gel: Began plugging at 8:30 pm on 2-14-01.

Heavy mud from 4550' to 900', then 50 sx, heavy mud to 330', then 50 sx, heavy mud to 40', then 10 sx to surface. Cement did circulate. Mousehole 10 sx, rathole 15 sx.

Plugging completed at 10:45 pm on 1-14-01 by Acid Services. Ticket # 03122.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: National Petroleum Reserves, Inc. (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.


(Signature) Gary M. Talbott
(Gary M. Talbott, Vice- President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 15th day of Feb, 2001 RECEIVED
STATE CORPORATION COMMISSION

FEB 16 2001

Pamela S. Fields CONSERVATION DIVISION
(Notary Public) Wichita, Kansas



My Commission Expires:

Form CP-4
Revised 12-92

OR

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG

Berry No. 1

LOCATION: Se Sw Se Section 23 T 26s R 14w
API: 15-151-22183-0000 Pratt County, Kansas

OWNER: National Petroleum Reserves, Inc.
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 02/06/01
COMPLETED: 02/14/01

TOTAL DEPTH: DRILLER 4550 FEET
LOGGER 4551 FEET

Ground Elevation: 1976
KB Elevation: 1985

LOG

0 -	31 FEET	Surface Sand
31 -	50 FEET	Clay
50 -	60 FEET	Fine Sand
60 -	93 FEET	Coarse Sand and Gravel
93 -	168 FEET	Sand
168 -	867 FEET	Red Beds and Shales
867 -	887 FEET	Anhydrite
887 -	4550 FEET	Limestone/Shales/Sandstones

CASING RECORDS

Spud at 8:30 am on 02-06-01. Drilled 12-1/4" hole to 310'. Ran 7 joints of new 20# 8-5/8" surface casing tally 295.12' set at 307' KB.
Cemented with 190 sx 60/40 Poz, 2% Gel, 3% CC, 1/4 lb. Celloflake per sack.
Plug down at 3:00 pm on 02-06-01 by Acid Services. Good returns. Ticket # 03198.

Received plugging orders from Steve Durrant on 2-13-01 at 8:45 am.
Plugged well as follows using 135 sx 60/40 Poz, 6% Gel: Began plugging at 8:30 pm on 2-14-01. Heavy mud from 4550' to 900', then 50 sx, heavy mud to 330', then 50 sx, heavy mud to 40', then 10 sx to surface. Cement did circulate. Mousehole 10 sx, rathole 15 sx.
Plugging completed at 10:45 pm on 1-14-01 by Acid Services. Ticket # 03122.

DEVIATION SURVEYS

1-3/4 degree(s) at 4353 feet

RECEIVED
STATE CORPORATION COMMISSION

FEB 16 2001

CONSERVATION DIVISION
Wichita, Kansas