


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pratt County. Sec. 24 Twp. 26 Rge. (E) 14(W)
Location as "NE/CNW/SW" or footage from lines 330' South & 330' West of E/4 Cor.
Lease Owner Cities Service Oil Company
Lease Name Bennett Well No. 1
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 28, 19 54
Application for plugging filed June 28, 19 54
Application for plugging approved June 28, 19 54
Plugging commenced June 28, 19 54
Plugging completed June 28, 19 54
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Arbuckle Depth to top 4522 Bottom 4560 Total Depth of Well 4560 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	832'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4560-300', heavy mud.
300-225', wood plug and hulls, 25 sacks cement.
225- 35', heavy mud.
35' to base of cellar, wood plug and hulls, 10 sacks cement.

WELL
STATE CORP.

CONSERVATION
WICHITA

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R. W. Rine Drilling Company
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
V. M. Conover (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V.M. Conover
Box 751, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of June, 19 54

N. B. Smith
Notary Public.

My commission expires March 12, 1955.

PLUGGING
FILE SEC 24 T 26 R 14W
BOOK PAGE 45 LINE 15

WELL RECORD

Company Cities Service Oil Co. Well No. 1 Farm Barnett
 Location 330' South and 330' West of S/4 Corner Sec. 24 T. 26 R. 14W
 Elevation 1955 (1953 Cr.) County Pratt State Kansas
 Drlg. Comm. June 10, 1954 Contractor R. W. Rine Drilling Company
 Drlg. Comp. June 27, 1954 Acid None
 T.D. 4560' Initial Prod. Dry Hole - Plugged and Abandoned June 28, 1954

CASINO RECORD:

8-5/8" @ 832' cemented with 450 ex cement

FORMATION RECORD:

sand & clay	0-240
red bed	310
red bed & shale	822
anhydrite	832
shale & shells	1350
salt, shale & shells	1845
shale & shells	2045
sandy lime & shale	2170
lime	2335
lime & shale	3365
lime	3630
lime, shale & sand	3735
lime & shale	3880
lime	3925
lime & chert	3956
lime	4155
lime & shale	4185
lime & chert	4230
lime & shale	4275
chert	4306
chert, shale & sand	4310
chert	4370
chert & lime	4402
lime & shale	4426
shale & sand	4480
shale & lime	4500
lime & shale	4520
lime	4560 T. D.

Topoka	3289'
Brown Limestone	3790'
Lansing	3819'
Mississippi	4250'
Kinderhook	4318'
Kinderhook Sand	4330'
Viola	4348'
Simpson Shale	4422'
Simpson Sand	4429'
Arbuckle	4522'
Penetration	38'
Total Depth	4560'

D. S. T. 3966-80, open 1 hr., rec. 30' mud with few specks oil; B.H.P. 1160#/30 mins.

D. S. T. 3999-4008, open 1 hr., rec. 60' slightly oil-cut muddy water; B. H. P. 1030#/30 mins.

D. S. T. 4252-60, open 1 hr., rec. 20' mud; B. H. P. 0#/30 mins.

D. S. T. 4260-4306, open 1 hr., rec. 55' gassy mud with slight show oil; B. H. P. 100#/30 mins.

D. S. T. 4316-40, open 1 hr., rec. 32' mud; B. H. P. 70#/30 mins.

D. S. T. 4340-71, open 1 hr., rec. 305' tacky salt wbr.; B. H. P. 1420#/30 mins.

D. S. T. 4371-4402, open 1 hr., rec. 773' salt water; B. H. P. 1190#/20 mins.

D. S. T. 4430-38, open 1 hr., rec. 40' mud; B. H. P. 1280#/30 mins.

D. S. T. 4451-80, open 1 hr., rec. 859' salt water; D. H. P. 1680#/30 mins.

SYFO: 250' 1°, 545' 0°, 1000' 1°, 1500' 1°, 2000' 1°, 3000' 1/2°, 3500' 1°, 4000' 1°.

PLUGGING
 FILE SEC 24 T. 26 R. 14W
 BOOK PAGE 45 LINE 15

FIVED
 JUL 3 - 1954
 DIVISION OF OIL AND GAS
 Wichita, Kansas