

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

C-NE-NW

COUNTY Pratt SEC. 26 TWP. 26S RGE. 14 XW
Location as in quarters or footage from lines:

Locate Well
correctly on above
Section Platt.

Lease Owner Bill Lake
 Lease Name Hemphill Well No. 1
 Office Address Box 286 Derby, Ks. 67037
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed 3-17-81
 Application for plugging filed 4-16-84
 Plugging commenced 4-16-84
 Plugging completed 4-18-84
 Reason for abandonment of well or producing formation
Not economical to produce

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Steve Durant gave orders
 Producing formation None produced Depth to top _____ bottom _____ T.D. 4625'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record


Formation	Content	From	To	Size	Put in	Pulled Out
		0	379	8 5/8	379'	0
		379	4519	4 1/2	4140'	76 jts.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Bridge Plugs at 3510', 3600', Top perfs 3461', top of cement 3400'. Another bridge plug at 4090'. Bottom hole plugging, sand at 3360', P B T D at 3510', dumped 4 sx. cement, shot casing off at 3109'. Top hole plugging: 3 sx. hulls, 10 sx. gel, 50 sx. cement, 10 sx. gel, 1 sx. hulls, 8 5/8" wiper plug, 100 sx. cement, 60/40 poz mix, 2% gel, 37% CC. Finished at 10:20 AM on 4-18-84, SIP 100#.

RECEIVED
STATE CORPORATION COMMISSION
APR 24 1984
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pratt Well Service, Inc.

STATE OF Kansas COUNTY OF Pratt, ss.
Judy Berry (employee of owner) or ~~(owner)~~ of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Judy Berry
 Box 847 Pratt, Ks. 67124
 (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of April, 1984
Charlene M. Dudrey
 Notary Public.

My Commission expires: 9/10/86