

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-151-20,777-00-00

LEASE NAME BERRY

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

_____ Ft. from S Section Line

_____ Ft. from E Section Line

SEC. 23 TWP. 26 SRGE. 14W(E) or (W)

LEASE OPERATOR PRATT WELL SERVICE, INC.

COUNTY PRATT

ADDRESS P.O. BOX 847

Date Well Completed 7/12/80

PHONE (316) 672-2531 OPERATORS LICENSE NO. 5893

Plugging Commenced 4/7/00

Character of Well OIL

Plugging Completed 4/10/00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 1999 (date)

by David Williams (KCC District Agent Name)

Is ACO-1 filled? not known If not, is well log attached? DO NOT HAVE ONE

Producing Formation Viola Depth to Top 1439 1/2 Bottom 4401 T.D. 4460

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Viola				4 1/2"		22 Jts.

MAY 10 2000

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each so Shot off 4 1/2" casing @ 917' from surface. Pulled 22 Jts of 4 1/2" casing, hooked up cement co. to 8 5/8" casing and pumped 300 lbs of hulls, 10 sxs gel, 50 sxs of 60/40 poz cement, 10 sxs gel, 100 lbs of hulls. Released wood plug and pumped 100 sxs of cement and closed in. Topped off with 2 sxs of #94 Portland cement.

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P.O. BOX 847 PRATT, KS 67124

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PRATT WELL SERVICE, INC.

STATE OF KANSAS COUNTY OF PRATT, ss.

APR 24 2000

Amy S. Robertson (Employee of Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Amy Robertson

(Address) P.O. Box 847 Pratt, KS 67124

SUBSCRIBED AND SWORN TO before me this 20th day of April 2000

Kevin C. Gates
Notary Public

My Commission Expires: 3/13/04

KEVIN C. GATES
Notary Public - State of Kansas
My Appt. Expires 3/13/04

Form CP-
Revised 05-8