

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

	1980		
1980	•		

Locate well correctly on above
Section Plat

Commanche County. Sec. 7 Twp. 35S Rge. 20 (E)W (W)
 Location as "NE/CNW&SW" or footage from lines 1980' from N. 1980 W
 Lease Owner Mesa Petroleum Co.
 Lease Name Tuttle Well No. 1-7
 Office Address Box 2009 Amarillo, Texas 79105
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed June 28 19 68
 Application for plugging filed June 29 19 68
 Application for plugging approved June 29 19 68
 Plugging commenced June 30 19 68
 Plugging completed July 3 19 68
 Reason for abandonment of well or producing formation non-economic

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph J. Warren
 Producing formation Morrow Depth to top 5570 Bottom 5600 Total Depth of Well 5691 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow	salt water	5570	5600	8 5/8	560'	none
	and gas			4 1/2	5991	4524

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
 Mixed and pumped 10 sacks cement--displaced w/mud laden fluid to 5300'; shot pipe at 5117', 4911', 4708', and 4510'.
 Pulled 140 joints of 4 1/2" casing. Pumped 25 sacks cement to 400' with mud.
 Cut off 8 5/8" casing and spotted 10 sacks cement in top.

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 24 1968
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lillard Casing Pulling Inc.
 Address PO Box 962 Woodward, Oklahoma

STATE OF Texas, COUNTY OF Potter, ss.
 J. L. FARRELL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *J. L. Farrell*
 Box 2009 Amarillo, Texas
 (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of July, 19 68

My commission expires 6-1-69 *27 Slife* Notary Public.



WELL LOG

COMPANY **Mesa Petroleum Company**

SEC. **7** T. **35S** R. **20W**

FARM **Tuttle**

NO. **1-7**

LOC. **1980'** from W & N Lines


TOTAL DEPTH **5691'**

COUNTY **Comanche**

COMM. **6-4-68**

COMP. **6-22-68**

CONTRACTOR **Garvey Drilling Company**



CASING **8 5/8" @ 560' w/750 sx**
4 1/2" @ 5690' w/150 sx

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

202' Surface Soil
560' Surface Sand
815' Red Bed
1090' Red Bed and Shale
1602' Red Bed and Shells
1947' Shale and Shells
2347' Shale and Lime
2705' Lime and Shale
2745' Lime
3014' Lime and Shale
3155' Shale and Lime
3270' Lime and Shale
3520' Shale and Lime
3795' Lime and Shale
3852' Shale and Lime
4002' Lime and Shale
4130' Lime
4607' Lime and Shale
4692' Lime
4889' Lime and Chert
5080' Lime
5116' Lime and Chert
5160' Lime
5225' Lime with Chert
5371' Lime
5565' Lime and Shale
5633' Lime and Sand
5691' Lime
5691' RTD

RECEIVED
STATE CORPORATION COMMISSION
SEP 3 1968
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } ss

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Tuttle No. 1-7 well.

Sam N. Stephens

Subscribed and sworn to before me this 27th day of June 19 68.

My Commission Expires: November 5th, 1969

Richard A. Doye
NOTARY PUBLIC