

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-033-20669-00-00

LEASE NAME Box Ranch

WELL NUMBER 1-12

4950 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 12 TWP. 35S RGE. 20 (X) or (W)

COUNTY Comanche

Date Well Completed 4/85

Plugging Commenced 10/3/89

Plugging Completed 10/6/89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Roberts & Murphy, Inc

ADDRESS P.O. 7125, Shreveport, LA., 71137-7125

PHONE# (318) 221-8601 OPERATORS LICENSE NO. 4145

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/3/89 (date)

by Mr Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Viola Depth to Top 6422 Bottom 6453 T.D. 6751

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Viola	Water	6422	6453	8 5/8	901	None
				5 1/2	6750	3615

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pumped 25 sack cmt w/2 sxs hulls to 6000-6221'. Shot pipe at 3615'. Pumped 50 sxs cmt from 950' to 785'. Pumped 35 sxs cmt from 400' to 285'. Pumped 10 sxs cement from 40' to 4'. Drilling mud was used for all plug displacement. Capped well by welding on steel plate.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent Casing Pulling Service License No. 6547

Address Box 506, Liberal, KS 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Roberts & Murphy, Inc

STATE OF Kansas COUNTY OF Pratt, ss.

Robert L. Moorehead

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Robert L. Moorehead

(Address) 1410 Western Ave., Pratt, KS 67124



SWORN TO before me this 4th day of December, 19 89

Julia Berry
Notary Public

My Commission Expires: Feb. 6, 1993