

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 2 TWP. 26N RGE. 11W E/W
Location as in quarters or footage from lines:
2310' FNL & 2310' FEL

Locate Well
correctly on above
Section Platt.

Lease Owner Bellwether Exploration Company
Lease Name Fulks Well No. 1
Office Address 1630 Welton, Suite 300, Denver, CO 80202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry
Date Well Completed 4/18/83
Application for plugging filed Yes
Plugging commenced 4/28/83
Plugging completed 4/28/83
Reason for abandonment of well or producing formation Dry

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bob Tarbutton
Producing formation None Depth to top _____ bottom _____ T.D. 4450'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>No oil or gas encountered</u>						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cement with 50-50 poz, 4% gel, 3% CaCl as follows:
40 sx @ 600'
40 sx @ 330'
set hulls & wood plug @ 40'. Filled to top with 10 sx. Circulate
15 sx in rathole. Circulate 5 sx in water well.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Wheatstate Oilfield Service

STATE OF Colorado COUNTY OF Denver, ss.
(employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
1630 Welton, Suite 300, Denver, CO
(Address)

SUBSCRIBED AND SWORN TO before me this 9TH day of May, 19 83

My Commission expires: May 5, 1984

Jaren Bacon RECEIVED
STATE CORPORATION COMMISSION
NOTARY PUBLIC

MAY 12 1983

CONSERVATION DIVISION
Wichita, Kansas



- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLERS' WELL LOG

Fulks # 1
 SW SW NE Sec. 2-26S-11W
 Pratt County, Kansas
 Commenced : 4-18-83
 Completed : 4-28-83
 Operator : Bellwether Exploration Company

Depth From	To	Formation	Remarks:
-0-	321	Surface sand, red bed, shale	Drilled to 321' 4-18-83. Ran 7 joints (283.28') of 8 5/8", 24# surface casing set @294'. Cemented with 100 sxs Lite, 3% CC, 100 sxs Common, 2% Gel, 3% CC. Plug down @11:00 P.M. on 4-18-83.
321	4450	Lime, Shale, Arbuckle	

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 04 1983
 CONSERVATION DIVISION
 Wichita, Kansas

4-28-83. R.T.D. 4450'. Plugged well with 40 sxs @600', 40 sxs @330', 10 sxs @40', 15 sxs for rat hole and 5 sxs in water well. Cement 50/50 poz A, 4% Gel, 3% CC. Plug down at 7:30 A.M. on 4-28-83. Halliburton tkt. #650645. State plugger Bob Tarbutton.


STATE OF KANSAS)
) ss
 COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

L. R. Belding
 L. R. BELDING VICE-PRESIDENT

My Commission Expires:
April 23, 1987



Darlene Butts
 Darlene Butts Notary Public