


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pratt County, Sec. 2 Twp. 26S Rge. 11W ~~XXX~~
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
1320' FNL and 1650' FEL
Lease Owner The National Oil Company
Lease Name Fulks Well No. 1
Office Address Suite 550, O.W. Garvey Bldg., Wichita
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole
Date Well completed March 4, 1977
Application for plugging filed Verbal Application 1977
Application for plugging approved Verbal Approval 1977
Plugging commenced March 4, 1977
Plugging completed March 4, 1977
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Buddy Metz
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4290'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	321'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,290 ft. (rotary total depth) to 300 ft. Set plug at 300 ft. and cemented with 35 sacks cement. Filled hole with heavy rotary mud from 300 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 15 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton ~~WELL~~ Well cementing pump truck through 4-1/2 inch drill pipe.

RECEIVED
STATE CORPORATION COMMISSION

MAR 11 1977


(If additional description is necessary, use BACK of this ~~STATE~~ ~~WICHITA~~ Kansas

Name of Plugging Contractor Halliburton Services
410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent (employee of owner) ~~XXXXXXXXXXXXXXXXXXXX~~
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 No. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of March, 1977



Elsie Willison
Elsie Willison - Notary Public.

My commission expires June 30, 1978

KANSAS GEOLOGICAL SOCIETY API NO. - 15-151-20,365
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY The National Oil Company


SEC. 2 T. 26S R. 11W
 LOC. 1320' FNL and
 1650' FEL

FARM Fulks

NO. 1

COUNTY Pratt

TOTAL DEPTH 4,290'
 COMM. February 21, 1977 COMP. March 4, 1977
 SHOT OR TREATED
 CONTRACTOR H-30, Inc.
 ISSUED March 10, 1977



CASING
 20 10
 15 8-5/8" 321' cemented w/325 sxs cement ELEVATION 1800' KB
 12 6
 13 5

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale and Lime	2,180'
Lime and Shale	2,517'
Shale and Lime	2,729'
Lime and Shale	3,530'
Lime	4,290'
Rotary Total Depth	4,290'

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 11 1977
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above and foregoing to
 be a true and correct log of the above described
 well as shown by the drilling reports.


H-30, INC.

Dean Britting

 Dean Britting

State of Kansas)
 County of Sedgwick) ss:

Subscribed and Sworn to before me a Notary Public
 in and for said county and state this 10th. day
 of March, 1977.



Elsie Willison

 Elsie Willison - Notary Public

My Commission Expires:
 June 30, 1978