

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pratt

County. Sec. 36 Twp. 25S Rge. 13 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NE

Lease Owner Bridgeport Oil Co. Inc.

Lease Name Harrel Well No. 6

Office Address 914 Central Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 19 19 49

Application for plugging filed April 21 19 49

Application for plugging approved April 23 19 49

Plugging commenced April 23 19 49

Plugging completed April 29 19 49

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production None 19 49

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. D. Stough, Great Bend, Kansas.

Producing formation Arbuckle Depth to top 4290 Bottom 4311 Total Depth of Well 4311 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface	Water	0	755	8 5/8	755	None
		0	4296	5 1/2	4296	2934

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with roak 4311 to 4290 - Dumped 5 sacks cement at 4290. Top cement at 4250. Filled with heavy mud to 260 bridge and 15 sacks cement 260 to 210'. Heavy mud to 25' - bridge & 10 sacks cement 25' to base of cellar.

RECEIVED
MAY 2 1949
STATE CORPORATION COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Bridgeport Oil Co. Inc.
Address 914 Central Bldg., Wichita 2, Kansas

STATE OF _____, COUNTY OF _____, ss.

_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____

(Address) _____

SUBSCRIBED AND SWORN to before me this 2nd day of May, 1949

My commission expires Aug. 2, 1950

Arduce L. Kessler
Notary Public.

PLUGGING
RUE SEC 36 T 26 R 13 W
BOOK 92 PAGE 27

15-151-10876-00-00

Company: Bridgeport Oil Co. Inc.

Sec. 36 Twp. 26S Rge. 13W

Farm: Harrel No. 6

Location: NE NE NE

Date started: March 24, 1949
Date completed: April 19, 1949

County: Pratt
Kansas

Rotary O - 4297
Cable - 4297-4311

Elevation: 1926

Casing Record:

8 5/8" @ 755' 400 sxs cem.
5 1/2" @ 4296 225 sxs cem.

O.	235	clay-sand & gravel
235	465	red rock
465	751	shale & shells
751	755	anhydrite
755	1340	shale & shells
1340	1495	Salt
1495	1715	shale & shells
1715	1780	Lime & shale
1780	2170	lime
2170	2200	shale & shells
2200	2220	lime
2220	2245	shale & shells
2245	2345	lime
2345	2470	shale & shells
2470	2495	lime
2495	2545	shale & shells
2545	2560	lime
2560	3215	shale & shells
3215	3470	lime
3470	3497	shale & lime shells
3497	3570	lime
3570	3695	lime & shells
3695	4130	lime & chert
4130	4138	shale
4138	4140	lime & chert
4140	4205	lime & shale
4205	4255	sand & shale
4255	4293	shale
4293	4311	lime
T.D.	4311	

TOPS	
Lansing-Kansas City	3707
Mississippian	4097
Kinderhook	4115
Viola	4126
Simpson	4181
Arbuckle	4290

RECEIVED
 Conservation-Dir.
 MAY 20 1949
 STATE CORPORATION
 COMMISSION
 KANSAS

At 4311 Acidized with 500 gal. Swabbed 373 bbl. water & 7 bbls. oil in 17 hrs.

Plugged and Abandoned

PLUGGING
 FILE SEC 36T26R13W
 BOOK PAGE 92 LINE 27