

STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,301-00-00

LEASE NAME Huff

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-35

990 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 35 TWP. 26S RGE. 11 (E) or (W)

COUNTY Pratt

LEASE OPERATOR Nash Oil & Gas

ADDRESS 1318 E First, Pratt, Kansas 67124

PHONE#(316) 672-7500 OPERATORS LICENSE NO. 31629

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

Date Well Completed 08-24-83

Plugging Commenced 10-27-95

Plugging Completed 10-30-95

The plugging proposal was approved on 10-27-95 (date)

by Steve Pfeifer (XCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Kansas City Depth to top 3872 Bottom 3938 T.C. 4530

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface			8 5/8	383	0
	Production			4 1/2"	4347'	1901

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, - from feet to feet each set
Bottom plug; sanded off to 3820'. 4 sks of cement. Allied mixed 300 lbs. of hulls, 10 sks gel, 50 sks of cement, 6 sks gel, 100 lbs. hulls. Released plug, 150 sks cement, 60/40Poz 6% gel
Maximum pressure 800lbs. Shut in pressure 400 lbs.

Name of Plugging Contractor D.S. & W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, Kansas 67525

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nash Oil & Gas NOV - 6 1995

STATE OF Kansas COUNTY OF Barton, ss.

Arthur P. Strube (Employee of Operator or Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Arthur P. Strube
(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED AND SWORN TO before me this 2 day of November, 1995

Bonnie L. Connell
Notary Public

My Commission Expires: 4-8-97

USE ONLY ONE SIDE OF EACH FORM

BONNIE L. CONNELL
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 4-8-97