

STATE OF KANSAS
STATE CORPORATION COMMISSION

**Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas**

WELL PLUGGING RECORD

NORTH

**Locate well correctly on above
Section Plat**

Pratt County. Sec. 31 Twp. 26 Rge. 11 (X) (W)
 Location as "NE/CNW%SW%" or footage from lines SE NE NE
 Lease Owner The Palmer Oil Corporation
 Lease Name Allen Well No. 1
 Office Address Union National Bank Building, Wichita 2, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed April 5 1953
 Application for plugging filed April 5, 1953
 Application for plugging approved April 5, 1953
 Plugging commenced April 5, 1953
 Plugging completed April 5, 1953
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was com-
 menced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. River
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4500 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 300 feet.
Plug at 300 feet - cemented with 20 sacks.
Plug at 35 feet - cemented with 10 sacks.

RECEIVED
STATE CORPORATIONS COMMISSION
APR 11 1953
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor The Palmer Oil Corporation
Address 415 Union National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Edgar E. Smith (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. *[Signature]*

(Signature) Eugene O. Mull
Union Nat'l. Bank Bldg., Wichita 2, Kansas
 (Address)

SUBSCRIBED AND SWORN to before me this 10 th day of April, 1953

My commission expires July 23, 1955.

Notary Public.



PLUGGING
FILE SEC 21 T 26 R 11W
BOOK PAGE 90 LINE 14

WELL LOG - ALLEN #1

WELL OWNER: The Palmer Oil Corporation

CONTRACTOR: The Palmer Oil Corporation

Commenced: 3/18/53

Completed: 4/5/53

RESULTS: Dry Hole

Location: SE NE NE
Section 31-26S-11W
Pratt County, Kansas
Elevation: 1827 R.B.

Casing Record

Figures Indicate Bottom of Formation

Shale & Red bed	385
Red bed	430
Red bed & Shells	745
Anhydrite	750
Shale & shells	1625
Lime & shale	2035
Broken Lime	2075
Shale & Lime	3135
Lime sandy	3230
Lime	3335
Shale & Lime	3625
Lime	4020
Lime & chert	4145
Lime	4230
Lime & shale	4259
Lime	4368
Sand & shale	4448
Arbuckle	4500 R. T. D.

8 5/8" - 481' cemented w/300 sacks

Formation Tops (R. B.)

Heebner	3420
Douglas Sand	3492
Brown Lime	3607
Lansing	3620
Mississippian	4082
Kinderhook	4123
Viola	4267
Simpson	4358
Arbuckle	4448
Total Depth	4500

This is to certify that the above is a true and correct log, according to the daily drilling reports.

THE PALMER OIL CORPORATION


By *Edgar E. Smith*

STATE OF KANSAS)
SEDGWICK COUNTY) ss:

Subscribed and sworn to before me, a Notary Public, in and for said County and State, this 10th day of April, 1953.

Iris Meyer
Notary Public

My Commission Expires: July 23, 1955.



RECEIVED
STATE OF KANSAS COMMISSION

APR 11 1953

CONSERVATION DIVISION
Wichita, Kansas