

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County. Sec. 28 Twp. 26S Rge. (E) 11 (W)

Location as "NE/CNW&SW&" or footage from lines SW NE NW
Lease Owner Stickle Drilling Company
Lease Name Koenemann Well No. 1
Office Address 1100 Bitting Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed 4 February 19 66
Application for plugging filed " " 19 _____
Application for plugging approved " " 19 _____
Plugging commenced " " 19 _____
Plugging completed " " 19 _____
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production -- 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. V. Elving
Producing formation -- Depth to top -- Bottom -- Total Depth of Well 4500 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Sands	Water	0	60'	8 5/8"	250	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy rotary mud was placed from total depth to 250 feet with the drill pipe.
A Wooden plug, 1/2 sack hulls and 25 sacks of cement were placed at 250'.
Heavy rotary mud was then placed to 40 feet.
A plug, 1/2 sack of hulls and 10 sacks of cement were placed at 40 feet.
Two sacks of cement were placed in the rat hole and 2 sacks were placed in the mouse hole.

RECEIVED
STATE CORPORATION COMMISSION

MAR 14 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stickle Drilling Company
Address 1100 Bitting Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sadgwick, ss.
Clifford M. Smith (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clifford M. Smith
1100 Bitting Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of February 19 66

My commission expires 17 February 1970

Charley V. Shank
Charley V. Shank Notary Public.

St+L

Stickle Drilling Company
Wichita, Kansas

14 February 1966
Wichita, Kansas

Drilling Contractor: Stickle Drilling Company
Date Commenced : 25 January 1966
Date Completed : 4 February 1966

Koenemann #1
SW NE NW 28-26S-11W
Pratt County, Kansas


DRILLER'S LOG

Depth figures indicate base of formation:

Surface soil	40
Shale and red bed	1130
Red bed	1140
Red bed and shale	1635
Shale and lime	1879
Lime and shale	2065
Lime	2245
Lime w/shale streaks	2313
Lime and shale	2400
Shale and lime	2930
Lime and shale	3185
Shale and lime	3495
Shale and sandy shale	3615
Lime and shale	3645
Lime	3718
Lime and shale	3790
Lime	4075
Lime and chert	4132
Lime	4165
Shale and lime	4275
Lime and chert	4312
Lime	4464
Dolomite	4500 TD

I, Clifford Smith, hereby certify that to the best of my knowledge and belief, the above is a true and complete Driller's Log of the Stickle Koenemann #1, SW NE NW 28-26S-11W, Pratt County, Kansas.


Clifford Smith


Wanda J. Steakley
My Commission Expires 16 January 1970

RECEIVED
STATE CORPORATION COMMISSION

MAR 14 1966

CONSERVATION DIVISION
Wichita, Kansas