

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

PRATT

County. Sec. 28 Twp. 26 Rge. 11 (E) 11 (W)

Location as "NE/CNW%SW%" or footage from lines SW NE SW

Lease Owner The Oil Capitol Corporation

Lease Name Eyers Well No. 1

Office Address 1001 First National Bldg., Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 7/25/55 19

Application for plugging filed 7/25/55 19

Application for plugging approved 7/25/55 19

Plugging commenced 7/25/55 19

Plugging completed 7/25/55 19

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4483 Feet

Show depth and thickness of all water, oil and gas formations.

| OIL, GAS OR WATER RECORDS | | | | CASING RECORD | | |
|---------------------------|---------|------|------|---------------|--------|------------|
| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
| Lansing | Water | 3718 | 3746 | 8 5/8 | 332 | none |
| Mississippi | Nothing | 4081 | 4091 | | | |
| Viola | Water | 4265 | 4280 | | | |
| Arbuckle | Water | 4443 | 4483 | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 300'
Set cement plug with 20 sacks cement and 1/2 sack hulls at 300'
Filled hole with heavy mud to 30'
Set cement plug with 10 sacks cement and 1/2 sack hulls at 30'
Top of last plug into bottom of cellar

RECEIVED
STATE CORPORATION COMMISSION
AUG 9 1955
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Iron Drilling Company
Address 1205 Philtower Building, Tulsa, Oklahoma

STATE OF OKLAHOMA, COUNTY OF TULSA, ss.
W. Keith Schuerman (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. Keith Schuerman
Tulsa, Oklahoma (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of August 19 55
Walter K Loop Notary Public.

My commission expires January 14, 1958

PLUGGING
FILE SEC. 28 T. 26 R. 11 W
BOOK PAGE 38 LINE 5

DRILLING RECORD

Well No. 1 Eyers
 SW NE SW Sec 28-26S-11W
 Pratt County, Kansas

Work Commenced 7/6/55
 Drilling Commenced 7/7/55
 Drilling Completed 7/24/55
 Work Completed 7/25/55

Casing Record

332' of 8-5/8" OD Surface Pipe
 cemented with 200 sacks.
 No Oil String - Dry Hole

WELL LOG

| | |
|----------------------|--------------|
| Subsoil & Sand | 0 to 180 |
| Red Bed | 180 to 380 |
| Red Bed & Shale | 380 to 605 |
| Red Bed | 605 to 705 |
| Anhydrite | 705 to 730 |
| Shale | 730 to 1040 |
| Shale & Shells | 1040 to 1230 |
| Shale & Lime Streaks | 1230 to 1270 |
| Shale & Shells | 1270 to 1440 |
| Salt | 1440 to 1520 |
| Shale & Shells | 1520 to 1655 |
| Shale & Lime | 1655 to 1700 |
| Lime | 1700 to 1780 |
| Lime & Shale | 1780 to 1905 |
| Lime & Shale | 1905 to 2140 |
| Shale & Lime | 2140 to 2740 |
| Lime & Shale | 2740 to 3475 |
| Lime | 3475 to 3570 |
| Lime & Shale | 3570 to 3635 |
| Lime | 3635 to 3713 |
| K.C. Lime | 3713 to 3746 |
| Lime & Shale | 3746 to 3767 |
| Lime | 3767 to 3815 |
| K.C. Lime | 3815 to 3855 |
| Lime | 3855 to 3916 |
| Lime & Shale | 3916 to 3955 |
| Lime | 3955 to 4022 |
| Lime & Shale | 4022 to 4079 |
| Miss. Chert | 4079 to 4103 |
| Miss. Chert & Shale | 4103 to 4135 |
| Shale & Lime | 4135 to 4163 |
| Shale | 4163 to 4265 |
| Conglomerate | 4265 to 4280 |
| Cherty Dolomite | 4280 to 4293 |
| Chert - Lime - Shale | 4293 to 4312 |
| Lime | 4312 to 4355 |
| Lime - Shale | 4355 to 4375 |
| Simp. Sand | 4375 to 4435 |
| Shale & Lime | 4435 to 4443 |
| Arbuckle | 4443 to 4480 |
| Lime | 4480 to 4483 |

C E R T I F I C A T I O N

STATE OF OKLAHOMA)
 COUNTY OF TULSA) SS

I, J. L. Stackpole, Office Manager
 of the Iron Drilling Company, Certify
 that the accompanying is a true and
 correct log of the above described
 well.

J. L. Stackpole

Subscribed to and Sworn before me
 this 3rd day of August, 1955.

D. Michal
 Notary Public

My Commission Expires
 Feb. 28, 1956

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 9 X 1955
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 PLK SEC 28 T 26 S 11W
 BOOK PAGE 138 LINE 5