

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 9 Twp. 26 Rge. 13 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE NW  
Lease Owner The Palmer Oil Corporation  
Lease Name Strack Well No. 1  
Office Address Union National Bank Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 3 1953  
Application for plugging filed June 3, 1953  
Application for plugging approved June 3, 1953  
Plugging commenced June 3, 1953  
Plugging completed June 3, 1953  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	389	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 275 feet.  
Set plug at 275' and cemented with 20 sacks cement.  
Mud to 40'. Plugged at 40 feet and cemented with 10 sacks.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor The Palmer Oil Corporation  
Address 415 Union National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
A. H. Smith (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. H. Smith  
Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of June, 1953.

My commission expires July 23, 1955.

RECEIVED  
STATE CORPORATION COMMISSION

Notary Public. *Paul Meyer*

JUN 1 24-2675-8 2-52-20M

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 9 T 26 R 1320  
PAGE 106 LINE 6

WELL LOG - SHRACK #1

WELL OWNER: The Palmer Oil Corporation

Location: NE NE NW  
Section 9-26S-13W  
Pratt County, Kansas  
Elevation: 1945 R. B.

CONTRACTOR: The Palmer Oil Corporation

Commenced: 5/18/53

Completed: 6/3/53

RESULTS: Dry Hole

Casing Record

Figures Indicate Bottom of Formation

8 5/8" - 389' cemented w/ 275 sax

Sand & shale	195
Shale & shells	389
Red bed & shale	800
Anhydrite	830
Shale & shells	1835
Lime & shale	3315
Lime	4251
Lime & shale	4292
Lime	4337
Cherty lime	4373
Sand & shale	4415

Formation Tops (R. B.)

Douglas Sand	3642
Brown Lime	3732
Lansing	3766
Mississippi	4195
Viola	4266
Simpson Shale	4386
Simpson Sand	4398
Total Depth	4415

DRILL STEM TEST - 4197-4217 - Tool open one hour. Recovered 150 feet gas cut mud and salt water. No BHP.

This is to certify that the above is a true and correct log, according to the daily drilling reports.

THE PALMER OIL CORPORATION

By Edgar E. Smith

STATE OF KANSAS )  
                          ) ss:  
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public in and for said County and State, this 10th day of June, 1953.

Jess Meyer  
Notary Public

My Commission Expires: July 23, 1955. RECEIVED PALMER OIL CORPORATION

JUN 12 1953

CONSERVATION DIVISION

**PLUGGING**  
FILE SEC 9 T 26 S 13W  
PAGE 104 LINE 6