

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-5-117

API NUMBER 15-151-01D80-00-00

LEASE NAME Woods

WELL NUMBER #1

500' Ft. from S Section Line

1980' Ft. from E Section Line

SEC 3 TWP 26S RGE 13W (E) or (W)

COUNTY Pratt

Date Well Completed 12-7-82

Plugging Commenced 9-22-87

Plugging Completed 9-24-87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR The Reach Group

ADDRESS 229 E. William Suite 500  
Wichita, Kansas 67202

PHONE#(316) 262-1515 OPERATORS LICENSE NO. 8572

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4340'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	770'	none
				4-1/2"	4316'	2761'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4030' and 4 sacks cement. Shot pipe @3038', 2837',

2761', pulled a total of 83 joints of 4-1/2" casing. Plugged surface with 2hulls,

15 gel, 1 hull, 50 cement, 10 gel, 1 hull, plug and 125 cement, 60/40 pos, 6% gel.

Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

Box 347

(Address) Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 29th day of Sept., 19 87

RECEIVED  
STATE CORPORATION COMMISSION  
Notary Public

My Commission Expires:



SEP 30 1987

Form CP-4  
CONSERVATION DIVISION  
Wichita, Kan. Revised 07-86