

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pratt County, Sec. 3 Twp. 26 Rge. 13 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW SW NE
Lease Owner Victor Drilling, Inc.
Lease Name Chance Well No. 1
Office Address 301 Koch Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed 2-11-52 19
Application for plugging filed 2-11-52 19
Application for plugging approved 2-11-52 19
Plugging commenced 2-11-52 19
Plugging completed 2-11-52 19
Reason for abandonment of well or producing formation no commercial shows
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 4470 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	385	left in hole

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy rotary mud from 4470 Total Depth to base of surface pipe.
Rock bridge 15 sx cement, mud to 35', 10 sx cement to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Victor Drilling, Inc.
Address 301 Koch Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Victor F. Reiserer (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Victor F. Reiserer

301 Koch Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of February, 1952.

Notary Public.

My commission expires July 16, 1955 23-8390-s 6-51-20M

PLUGGING
FILE SEC 3 T 26 R 13
BOX PAGE 43 LINE 41

FEB 16 1952

Victor Drilling, Inc.

#1 Chance

NW SW NE 3-26S-13W
Pratt County, Kans.

Spuds: 1-14-52 8 5/8" @ 385' 200 sx
Comp: 2-11-52

Elev. 1929 KB

0-380 surface gravel and shale
 1010 surface shale & red bed
 1440 shale & sand
 1730 red bed & shale
 1800 salt bed & shale
 1815 lime & shale
 1980 lime & shale
 2070 lime & shale
 2235 lime
 2314 lime
 2420 shale & lime
 2550 shale & lime
 2655 shale
 2800 shale
 2985 shale
 3110 lime & shale
 3215 lime & shale
 3285 shale & lime
 3360 shale & lime
 3445 lime
 3523 lime & shale
 3540 lime & shale
 3610 lime & shale
 3702 shale & lime
 3738 shale & lime
 3768 lime & shale
 3816 lime
 3849 lime & shale
 3876 shale & lime
 3889 lime & shale
 3910 lime & chert
 3950 lime
 3983 lime
 4014 lime
 4049 lime
 4085 lime & chert
 4115 lime & chert
 4135 lime
 4180 shale & lime
 4209 shale & lime
 4219 chert & lime
 4229 chert & lime
 4251 chert & lime
 4265 lime & chert
 4287 lime & chert
 4305 cherty lime
 4324 chert & lime
 4357 sandy lime
 4382 shale, lime & sand
 4408 lime & shale
 4442 sandy shale & lime
 4470 Arbuckle lime
 4470 Total Depth

FORMATION TOPS

Heebner	3555
Brown Lime	3718
Lansing	3744
Mississippian	4174
Viola	4221
Simpson	4331
Arbuckle	4420

FEB 16 1952

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

I, Victor F. Reiserer swear that the foregoing statements are true to the best of my knowledge.

PLUGGING
 FILE SEC 3 T 26 R 13W
 BOX PAGE 43 LINE 45

Victor F. Reiserer
 Victor F. Reiserer

Subscribed and sworn to before me a notary public this 14th day of February, 1952.

My commission expires 7-16-55

Alma E. Ross
 Notary Public