

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21278-00-00

LEASE NAME McOster #1

WELL NUMBER _____

SPOT LOCATION SE NW NW

SEC. 9 TWP. 26S RGE. 11W (E) or (W)

COUNTY Pratt

Date Well Completed _____

Plugging Commenced 1-20-84

Plugging Completed 1-26-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR J.A. Allison

ADDRESS 300 W. Douglas Suite 305 Wichita, Ks. 67202

PHONE # (316) 263-2241 OPERATORS LICENSE NO. 5027

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4437'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	290'	none
				5-1/2"	4147'	2976'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped bottom with 40 sacks cement to 3900', well was flowing, pumped 25 sacks gel and 25 sacks of weight mud down annulus. Shot casing @3224', 2976' and pulled a total of 82 joints (2976') of 5-1/2" casing. Plugged surface with 3 hulls, 20 gel, 50 cement, 10 gel, 1 hull, released plug and displaced with 125 sacks cement, 60740 pos, 2% gel, 3% cc. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STATE CORPORATION COMMISSION

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

FEB 03 1984

SUBSCRIBED AND SWORN TO before me this 31 day of January, 1984

CONSERVATION DIVISION
Wichita, Kansas

My Commission expires: _____



Irene Hoover
Notary Public