

15-185-30364-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

*J*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

March 19, 1968.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 20 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Wayne E. Walcher

Complete Address: 809 Central Bldg., Wichita, Kansas, 67202

Lease Name Horstman Well No. #1

Location SE-NE-SW Sec. 26 Twp. 22 Rge. 14W (E) (W) W

County Stafford Total Depth 3875 ft.

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Santa Fe Pipe & Supply

Address: Box 562 Great Bend, Kansas License No. 574

Operation Completed: Hour 10:AM Day 19 Month March Year 1968

The Above well was plugged as follows:

254 ft of 8 5/8" surface pipe circulated with cement. Top perforation  
at 3586 ft. Sand to 3550 ft. & 4 sacks cement. Mud to 250 ft. 10sft.  
rock bridge, 6 sacks cement as overnite bridge. Hole bailed down  
& 19 sacks cement. Mud to 40 ft., 10 ft. rock bridge & 10 sacks cement  
to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: Hummer Justice  
Well Plugging Supervisor

INVOICED

D.A.E. 3/20/68  
INV. NO. 7449-u