

1080511

15-185-00550-00-01

API NUMBER 15- Completed 12-4-53

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NE SE, SEC. 26, T 22 S, R 14 ~~W~~ ~~EX~~

1650 feet from S section line

990 feet from E section line

Lease Name Smith "J" Well # 1

County Stafford 125.61

Well Total Depth 3865 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 267

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Operator: Petroleum, Inc.
Name & Address: P. O. Box 1447
Great Bend, KS 67530

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address P. O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10:00 am Day: 8 Month: April Year: 19 86

Plugging proposal received from Deacon Pulley

(company name) Rockhold (phone) 316-792-2506

were: 5 1/2" at 3863' PBD 3670' Perfs at 3817-19'; 3695-3700'; 3640-45'; 3572-75'; 3591-97'

1st plug sand back to 3520' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 120 sx cement.

Plugging Proposal Received by Dan Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:45 am Day: 8 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sand back to 3520' and dump 5 sx cement on top of sand

through bailer, 2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 120 sx cement.

RECEIVED STATE CORPORATION COMMISSION

APR 13 1986

4-13-86
CONSERVATION DIVISION
Wichita, Kansas

Maximum pressure 500 psi and shut in 250 psi

Remarks: Recovered 1480' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Sun.

(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby do (or not) observe this plugging.

APR 15 1986

DATE

Signed J. A. [Signature] (TECHNICIAN)

INV. NO. 13419