

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-21561-00-00  
Spot: W2SWNE Sec/Twnshp/Rge: 28-8S-25W  
3296 feet from S Section Line, 2510 feet from E Section Line  
Lease Name: CULLEY A Well #: 1  
County: GRAHAM Total Vertical Depth: 4392 feet

Operator License No.: 31000  
Op Name: PRATER OIL & GAS OPERATIONS, INC.  
Address: 906 WILLIAM WAY  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4151		150 SX
SURF	8.625	250		190 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/21/2014 9:00 AM  
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.  
Proposal Rcvd. from: DON CHRISLER Company: PRATER OIL & GAS OPERATIONS Phone: (785) 672-2667

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/21/2014 3:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforations: 245', 1356' and 2215'.  
Ran tubing to 3942' and pumped 125 sx cement. Fluid circulating out of braden head and backside. Pulled tubing to 2113' and pumped 100 sx cement. Pulled tubing to 607' and pumped 60 sx cement. Cement circulated. POOH. Hooked to casing and pumped 100 sx cement. Circulated cement out the braden head and shut in.

GPS: 39.32961 -100.11523

Perfs:

Top	Bot	Thru	Comments
4092	4093		
3962	3965		

Received  
KANSAS CORPORATION COMMISSION  
SEP 02 2014  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING TICKET # 63712

Plugged through: TBG

District: 04

Signed Ray Dinkel  
9.9.14 CKM (TECHNICIAN) CM

AUG 25 2014