

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21945-00-00
Spot: S2NWNWNW Sec/Twnshp/Rge: 10-35S-7W
500 feet from N Section Line, 330 feet from W Section Line
Lease Name: NANCY 3507 Well #: 1-10
County: HARPER Total Vertical Depth: 5362 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4940		
PROD	5.5	5362	2496	325 SX
SURF	9.625	850		234 SX
T1	2.875	5060		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/17/2014 4:00 PM
Plug Co. License No.: 34982 Plug Co. Name: TITAN WELL SERVICE, LLC
Proposal Rcvd. from: ANTHONY Company: TITAN WELL SERVICE Phone: _____

Proposed
Plugging
Method:

CIBP 4770' & 5 SKS. 50 SXS 1300'. 50 SXS @ 900'. CIRC 300' TO 0'.

Plugging Proposal Received By: _____ WitnessType: PARTIAL
Date/Time Plugging Completed: 07/17/2014 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

CIBP @ 4775 & 5 SKS CEMENT. LOAD CASING WITH PLUG MUD. REC CASING FROM 2496'. RAN TUBING TO 1300' SPOTED 50 SXS, PULLED TUBING TO 900' SPOTTED 60 SXS. PULLED TO 300' & CIRC'D CEMENT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
4952	4962		

Received
KANSAS CORPORATION COMMISSION
SEP 02 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND COMMON CEMENT.

Plugged through: TBG

District: 02

Signed 
9.9.14 ckm (TECHNICIAN)

VJK