

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-24234-00-00
Spot: NWNWNWSE Sec/Twnshp/Rge: 22-9S-16W
2380 feet from S Section Line, 2320 feet from E Section Line
Lease Name: CASEY ET AL Well #: 1-22
County: ROOKS Total Vertical Depth: 3783 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	305		175 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/04/2014 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 305 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 08/04/2014 3:45 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @3657 w/50 sx
2nd plug @1325 w/50 sx
3rd plug @875 w/100 sx
4th plug @350 w/50 sx
5th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Received
KANSAS CORPORATION COMMISSION
SEP 02 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY

Plugged through: DP

District: 04

Signed C. Morris
9.9.14 ckm (TECHNICIAN)

AUG 25 2014