

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20762-00-01
Spot: SWSEWNE Sec/Twnshp/Rge: 10-13S-32W
1168 feet from N Section Line, 1840 feet from E Section Line
Lease Name: TEETER Well #: 3-10
County: LOGAN Total Vertical Depth: 4748 feet

Operator License No.: 7311
Op Name: SHAKESPEARE OIL CO., INC.
Address: 202 W MAIN ST
SALEM, IL 62881

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4600		150 SX
SURF	8.625	223		165 SX

Well Type: SWD UIC Docket No: D30449.0 Date/Time to Plug: 08/22/2014 9:30 AM

Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.

Proposal Rcvd. from: DON WILLIAMS Company: SHAKESPEARE OIL CO. Phone: (618) 548-1585

Proposed Plugging Method: 8 5/8" surface casing set at 223' w/165 sx cement. 4 1/2" production casing set at 4600' w/150 sx cement. TD 4748'. PBTD 4552'. Port collar set at 2495' w/350 sx cement. Perforations: 4471' - 4475'. CIBP set at 2450'. Perforations 4471' - 4475' were not plugged. 4 1/2" casing was not plugged back with cement. Converted to Cedar Hills SWD well. Perforations: 2084' - 2184'. The well failed an MIT on 07/24/2014. 4 1/2" casing rough, packer failed to set W/I 50' above perforations. Attempted to drill out CIBP at 2450'. Drilled for 2 days with no success. The operator decided to plug well. District office approval by Case Morris on 08/21/14.

Plugging Proposal Received By: CASE MORRIS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 08/22/2014 11:50 AM

KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 2432' and pumped 80 sx cement w/o hulls. Pulled tubing to 1250' and pumped 100 sx cement w/450 # hulls. Cement to surface. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 15 sx cement. Pressured to 450 psi and shut in. Cement visible in 8 5/8" surface casing.

GPS: 38.94255 -100.85831

Perfs:

Top	Bot	Thru	Comments
4471	4475		
2084	2184		

Received
KANSAS CORPORATION COMMISSION
SEP 02 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENT SERVICES TICKET # 64,206

Plugged through: TBG

District: 04

Signed

Darrel Dipman
(TECHNICIAN)

cc: uic

9.9.14 ckm

CM

AUG 25 2014

Form CP-2/3