

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21042-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 15-14S-10W
1713 feet from S Section Line, 4704 feet from E Section Line
Lease Name: HANZLICEK Well #: 8
County: ELLSWORTH Total Vertical Depth: 3020 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2830		
PROD	5.5	3019		75 SX
SURF	8.625	285		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/03/2014 10:30 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN BUEHLER Company: TRANS PACIFIC OIL CORP Phone: (785) 483-1821

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 09/03/2014 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SET CIBP @ 2830' AND CAP WITH 2 SXS CEMENT. PERFORATE AT 1250', 900', AND 335'. RUN TUBING TO 1250' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 900', LET SET AWHILE AND ATTEMPT TO TAG - COLD NOT MAKE ABSOLUTE TAG. RUN TUBING BACK IN TO 1400' AND CIRCULATE CEMENT BACK TO SURFACE, GETTING OUT SOME OF BOTTOM SALT PLUG. PULL TUBING OUT AND TOP OFF. SWAGED ON TO 5.5" AND PUMPED UP TO 300#S - SHUT IN, THEN CONNECTED TO SURFACE AND PRESSURED UP TO 300#S ALSO - SHUT IN ALSO.

Perfs:

Top	Bot	Thru	Comments
2942	2954		CSG
2932	2936		CSG
2871	2893		CSG

Received
KANSAS CORPORATION COMMISSION
SEP 09 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60/40 POZ 4% GEL. QUALITY WELL TICKET #545. PERF TECH #12122.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)
9.9.14cm

JK