

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21243-00-00  
Spot: SWNESW Sec/Twnshp/Rge: 12-29S-10W  
1650 feet from S Section Line, 1650 feet from W Section Line  
Lease Name: WEBER Well #: 1  
County: KINGMAN Total Vertical Depth: 4575 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2634	1710	75 SX
SURF	8.625	329		250 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/12/2014 4:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Revd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (316) 262-3596

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL  
Date/Time Plugging Completed: 08/12/2014 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

PUMPED 25 SXS CEMENT WITH 100 LBS OF HULLS 3% CC FOR BOTTOM PLUG, TAGGED TOC @ 2100'. CUT CASING PIPE OFF @ 1710' PULLED CASING TO 1500' SPOTTED 35 SXS CEMENT 3% CC & 100 LBS HULLS. PULLED CASING TO 1000' SPOTTED 35 SXS CEMENT. PULLED CASING TO 380' CIRCULATED TO SURFACE WITH 140 SXS CEMENT.

Perfs:

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR JOB.

Plugged through: CSG

Received  
KANSAS CORPORATION COMMISSION

SEP 02 2014

CONSERVATION DIVISION  
WICHITA, KS

District: 02

Signed

*B. J. Hope*

9.9.14CKM (TECHNICIAN)