

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21448-00-00
Spot: S2NWNE Sec/Twnshp/Rge: 12-29S-10W
990 feet from N Section Line, 1980 feet from E Section Line
Lease Name: HOOVER Well #: 2
County: KINGMAN Total Vertical Depth: 2592 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2592		
PROD	4.5	2597	1740	75 SX
SURF	8.625	250		250 SX
SURF	8.625	329		300 SXS CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/15/2014 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (316) 262-3596

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL
Date/Time Plugging Completed: 08/15/2014 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

PUMPED BOTTOM PLUG TAGGED TOP OF CEMENT @ 2000'. CUT CASING PIPE OFF @ 1750' PULLED CASING TO 1500' SPOTTED 35 SXS CEMENT WITH 3% CC & 100 LBS HULLS. PULLED CASING TO 1000' SPOTTED 35 SXS CEMENT. PULLED CASING TO 300' CIRCULATED TO SURFACE WITH 120 SXS CEMENT. NEXT DAY: TAGGED TOC @ 120' - RAN 1 INCH INTO 100' PUMPED 30 SX CEMENT TO SURFACE.

Perfs:

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT ALSO.

Plugged through: CSG

Received
KANSAS CORPORATION COMMISSION

SEP 02 2014

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

B. J. Hope

9.9.14 cpm

(TECHNICIAN)