

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-24226-00-00
Spot: SESENWNE Sec/Twnshp/Rge: 22-6S-18W
1250 feet from N Section Line, 1340 feet from E Section Line
Lease Name: KOLLMAN TRUST 'A' UNIT Well #: 1-22
County: ROOKS Total Vertical Depth: 3598 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	218		150 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/21/2014 12:00 AM

Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC.

Proposal Rcvd. from: GEORGE Company: SHIELDS OIL PRODUCERS INC. Phone: (785) 735-4665

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS
Date/Time Plugging Completed: 08/21/2014 3:00 PM

WitnessType: NONE
KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @1500 w/50 sx
2nd plug @875 w/100 sx
3rd plug @275 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: GLOBAL

Plugged through: DP

Received
KANSAS CORPORATION COMMISSION
SEP 02 2014
CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Cum Morris
CCM 9/9/14 (TECHNICIAN)

AUG 25 2014