

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26693-00-00
Spot: SWNWSESW Sec/Twnshp/Rge: 8-14S-19W
760 feet from S Section Line, 3640 feet from E Section Line
Lease Name: GOTTSCHALK Well #: 1
County: ELLIS Total Vertical Depth: 3870 feet

Operator License No.: 3194
Op Name: TRI UNITED, INC
Address: 950 270TH AVE
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3860		130 SX
SURF	8.625	206		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/15/2014 2:30 PM
Plug Co. License No.: 3194 Plug Co. Name: TRI UNITED, INC
Proposal Rcvd. from: EUGENE LEIKER Company: TRI UNITED, INC Phone: (785) 628-3670

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/15/2014 8:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Cut casing at 2087'. Pulled casing to 1920' and pumped 125 sx cement w/200 # hulls. Pulled casing to 1250' and pumped 40 sx cement w/100 # hulls. Pulled casing to 860' and pumped 100 sx cement w/200 # hulls. Pulled casing to 350' and pumped 100 sx cement. Circulated cement and filled cellar. POOH and cellar stayed full.
Cut casing at 2087' leaving 1773' of 5 1/2" casing in well.

GPS: 38.84385 -099.46050

Perfs:

Top	Bot	Thru	Comments
3860	3870		
3713	3717		
3536	3540		

Received
KANSAS CORPORATION COMMISSION
AUG 27 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: GLOBAL CEMENTING TICKET # 1424

Plugged through: CSG

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

9.9.14 ckm

AUG 21 2014