

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-21829-00-00  
Spot: S2SWNE Sec/Twnshp/Rge: 4-18S-25W  
2980 feet from S Section Line, 2062 feet from E Section Line  
Lease Name: REED Well #: 6  
County: NESS Total Vertical Depth: 4275 feet

Operator License No.: 31788  
Op Name: VEENKER RESOURCES, INC.  
Address: PO BOX 14339  
OKLAHOMA CITY, OK 73113

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4279	0	WITH 150 SX CMT
RBP		3905		
SURF	8.625	301		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/19/2014 1:00 PM  
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.  
Proposal Rcvd. from: HAL Company: CHEYENNE WELL SERVICE, INC. Phone: (785) 798-2282

Proposed Plugging Method: SAND TO 4000' WITH 5 SX CMT. PLUG AT 1650' WITH 50 SX CMT. PLUG AT 1100' CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/19/2014 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 20 SX CMT AT 3050' ON TOP OF STUCK PACKER AT 3084'. RBP @ 3905'. SQUEEZED LEAKS AT 3216'-3600' WITH 250 SX CMT. PERFORATE 2 HOLES AT 1650' & 2 HOLES AT 1100'. SPOT 50 SX CMT AT 1650'. CLOSE ANNULUS AND PRESSURE TO 500# TO FORCE CMT INTO PERFS. TOOH W/TBG. CIRCULATE CMT TO SURFACE THROUGH THE PERFS AT 1100' USING 305 SX CMT LEAVING THE 5 1/2" CASING AND 5 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
4279	4295	OH	
4050	4097		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Ken Jehlik (TECHNICIAN)  
Received  
KANSAS CORPORATION COMMISSION

RECEIVED  
AUG 22 2014  
KCC DODGE CITY

SEP 02 2014  
CONSERVATION DIVISION  
WICHITA, KS