

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-27015-00-00
Spot: SESWSENW Sec/Twnshp/Rge: 23-26S-18E
2500 feet from N Section Line, 1800 feet from W Section Line
Lease Name: HARNER Well #: N-30A
County: ALLEN Total Vertical Depth: 840 feet

Operator License No.: 5491
Op Name: W & W PRODUCTION COMPANY, GEN
Address: 1150 HWY 39
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	0		0 SX
PROD	2	839		
SURF	8	0		0 SX
SURF	8	20		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/04/2014 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE WIMSETT Company: _____ Phone: (620) 431-4137

Proposed Plugging Method: Run 1" inside 2" to TD 840' & circulate cement to 0. Run 1" outside of 2" to TD 840' & circulate cement to 0. No Pit.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 04/04/2014 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report: Ran 1" pipe inside the 2" casing to 839'. Pump cement from 839' to surface using 37 sacks of Portland Cement. Pulled out 1" pipe. Ran 1" pipe outside of the 2" casing to 769'. Pump cement from 769' to surface using 131 sacks of Portland Cement. Pulled out 1" pipe out of the well. Topped the well off with cement. A total of 168 sacks of portland cement was reported used to plug this well.

Perfs: _____
RECEIVED
SEP 02 2014
KCC Chanute Dist. #3
RD
Received
KANSAS CORPORATION COMMISSION

Remarks:
Plugged through: TBG

SEP 05 2014
CONSERVATION DIVISION
WICHITA, KS

District: 03 Signed: _____ (TECHNICIAN)
9-9-14 CCM