

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-03384-00-00

Spot: SWSENESEW

Sec/Twnshp/Rge: 23-26S-18E

3800 feet from N Section Line, 2000 feet from W Section Line

Lease Name: HARNER

Well #: M-37

County: ALLEN

Total Vertical Depth: 840 feet

Operator License No.: 5491

Op Name: W & W PRODUCTION COMPANY, GEN

Address: 1150 HWY 39
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	0		0 SX
PROD	2	843		
SURF	8	0		0 SX
SURF	8	20		

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 04/08/2014 12:00 AM

Plug Co. License No.: 5491

Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP

Proposal Rcvd. from: MIKE WIMSETT

Company:

Phone: (620) 431-4137

Proposed
Plugging
Method:

Run 1" inside 2" to TD 840' & circulate cement to 0. Run 1" outside of 2" to TD 840' & circulate cement to 0. No Pit.

Plugging Proposal Received By:

WitnessType: NONE

Date/Time Plugging Completed: 04/08/2014 8:00 AM

KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe inside the 2" casing to 843'. Pump cement from 843' to surface using 30 sacks of Portland Cement. Pulled 1" pipe out of the 2" casing. Ran 1" pipe outside of 2" casing to 67'. Pump cement from 675' to surface using 133 sacks of Portland Cement. Pulled out 1" pipe out and topped the well off with cement. A total of 163 sacks of portland cement was reported used to plug this well.

RECEIVED

SEP 02 2014

KCC Chanute Dist. #3

RD

Received
KANSAS CORPORATION COMMISSION

SEP 05 2014

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed

(TECHNICIAN)

9.9.14 ocm