

DISTRICT CONSERVATION AGENT'S REPORT
15-151-10879-00-00

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 31-8

LOCATION SW-NE-NE

SEC. 36 TWP. 26 RGE. 13. W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Harrell

Operator Bridgport Oil Co., Inc. Address #914 Central Bldg. Wichita-Kans

Field _____ County Pratt

Total Depth 4329 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 477 ft. circulated with cement.
5 1/2" casing set at 4314 ft. - Plugged back to 3720 ft.
with Lane Wells Plug & Chat - Dumped 4 sacks cement
at 3720 ft. - Shot off & pulled 5 1/2" casing - Filled with
mud to 250 ft. Set bridge & 15 sacks cement at 250 ft.
Mud to 30 ft. - Bridge & 10 sacks cement at the surface
Patterson & Son - Pipe Pulling - Contractors

RECEIVED C. M. Stovall
District Conservation Agent

Conservation Div.

Date 11-12-48

PLUGGING
FILE SEC 36 TWP 26 RGE 13. W
BOOK PAGE 31 LINE 8

NOV 15 1948
11-15-48
STATE CORPORATION
COMMISSION
KANSAS