

15-151-10878-00-00

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 61-7

LOCATION SW-NE-NE

SEC. 36 TWP. 26 RGE. 13-W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Marcell

Operator Bridgeport Oil Co. Inc. Address 714 Central Bldg - Wichita - Kans.

Field \_\_\_\_\_ County Pratt

Total Depth 4340 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 10 3/4 - 441 ft - Circulated with cement -  
5 1/2 casing set at 4329 ft - Plugged back from  
bottom to 3880 ft - Dumped 5 sacks of cement at 3880 ft -  
Shot off & Pulled 5 1/2 casing - Filled with mud to  
250 ft - Bridge & 20 sacks of cement - Mud to 30 ft  
Plug & 10 sacks cement at the surface.  
Patterson & Son - Pipe Pulling - Contractors*

RECEIVED C. H. Stough -  
District Conservation Agent

Conservation Div. Date 11-1-48

NOV 5 1948  
11-5-48  
STATE CORPORATION  
COMMISSION  
KANSAS

**PLUGGING**  
FILE SEC 36 T 26 R 13W  
PAGE 31 LINE 8