

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-151-10880-00-00

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name H & H Supply Company

Complete Address: Box 94173, Oklahoma City, Oklahoma

Lease Name Harrel "A" Well No. # 3

Location SW SE NE Sec. 36 Twp. 26 Rge. 13 (E) (W) W

County Pratt Total Depth 4311'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Gayle E. Toland

Address: Box 94336, Oklahoma City, Oklahoma License No. 539

Operation Completed: Hour 1:30 PM Day 25th Month June Year 1965

The Above well was plugged as follows:

478' of 8 5/8" surface pipe, cement circulated. 4311' of 5 1/2" long string,
cemented with 225 sacks. Plug was pushed to 3873, and 10' of sand bridge,
and cemented with 5 sacks. Fluid was up in the hole. 13 bbls. of drilling
mud was pumped in the 5 1/2" at 450', and 35 sacks of cement was pumped in
5 1/2" at 330'. Hole was bailed down to 40', bridge plug set on fluid at 40',
and 10' of rock bridge, and cemented with 10 sacks to the base of the
cellar. 1800' of 5 1/2" long string was recovered from the hole.

RECEIVED

I hereby certify that the above well was plugged as herein stated.

INVOICED

JUN 28 1965

Signed: Annie Elving
Well Plugging Supervisor

DATE 6/28/65
CONSERVATION DIVISION
INV. NO. 1366-W Wichita, Kansas