

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 26 1966  
1-26-66  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Hinkle Oil Company

Complete Address: 1016 Union Center Bldg., Wichita, Kansas

Lease Name Petrowsky Well No. # 2

Location NW SE NW Sec. 10 Twp. 26 Rge. 12 (E) (W) W

County Pratt Total Depth 4283'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 4:30 PM Day 25th Month Jan. Year 1966

The Above well was plugged as follows:

347' of 8 5/8" surface pipe, cemented with 320 sacks. 4274' of 5 1/2" long  
string, cemented with 100 sacks. This is an open hole. Bottom of the  
hole was sanded to 4260', and cemented with 5 sacks, through the dump  
bailer. 3630' of 5 1/2" long string was recovered from the hole. Fluid  
in the hole was bailed down to 250', bridge plug and rock bridge from  
250' to 240', and cemented with 25 sacks. Hole was filled with mud to  
40', rock bridge from 40' to 30', and cemented with 10 sacks to the  
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/26/66

INV. NO. 2644-W

Signed: Archie Elving  
Well Plugging Supervisor