

15-151-19064-0000

Form CP-3
Rev. 6-26-62



KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 1 1963
10-1-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Halliburton Oil Producing Co.

Complete Address: 520 Cameron Bldg., Oklahoma City, Oklahoma

Lease Name Repp Well No. # 1

Location SE SW NE Sec. 10 Twp. 26 Rge. 12 (E) (W) W

County Pratt Total Depth 4310

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractors: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 2:30PM Day 29th Month Sept. Year 1963

The Above well was plugged as follows:

344' of 8 5/8" surface pipe, cemented with 200 sacks, 3800' of 5 1/2" long
string, cemented with 140 sacks. Plugged back to 3770'. Top perforation
3535'. Bottom of hole was sanded to 3500', cemented with 5 sacks. Fluid
level was up in hole. Plug was set at 300', 10' rock bridge, 4 sacks of
cement was mixed in barrel and put on plug through dump bailer, and let
set over night. Next morning hole was bailed down and 16 sacks cement
was added to plug. Hole was filled with mud to 40', 10' rock bridge,
cemented with 10 sacks to base cellar. 3010' of 5 1/2" long string was
recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 10-1-63

INV. NO. 7827-W