

15-151-18684-0000

Form GP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1964
10-12-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Champlain Oil & Refining Co.

Complete Address: Post Office Box 308 Ellinwood, KANSAS

Lease Name Miskimen Well No. #2

Location Sw-Ne-Se Sec. 32 Twp. 26 Rge. 12 (E) (W) W

County Pratt Total Depth 4298

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Co.

Address: Box 304 Great Bend, KANSAS License No. 2

Operation Completed: Hour 530 Day PM Month Oct. 6 Year 1964

The Above well was plugged as follows:

Use 800' of 10 3/4" Surface Pipe cemented with 450 sacks of cement. 4270' of
of 5 1/2" Long String cemented with 225 sacks cement. Top Perforation; 4177 sand
to 4160 cemented with 5 sacks; mud to 250 feet. 10 ft Rock Bridge, 35 sacks cement;
mud to 40 feet; 10 feet Rock Bridge, 20 Sacks cement to base of cellar.
2070 feet of 5 1/2" recovered.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 10/12/64
INV. NO. 9969-42

Signed: [Signature]
Well Plugging Supervisor