

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 28 1964
7-28-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Champlin Oil & Refining Company

Complete Address: P. O. Box 308, Ellinwood, Kansas

Lease Name Miskimen Well No. # 1

Location App. C NW SE Sec. 32 Twp. 26 Rge. 12 (E) (W)W

County Pratt Total Depth 4305

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Company

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 5:00PM Day 27th Month Sept. Year 1964

The Above well was plugged as follows:

800' of 10 3/4" surface pipe, cemented with 450 sacks. 4284' of 5 1/2" long string, cemented with 175 sacks. Plug back to 4256'. Top perforation 3823'. Bottom plug was pushed to 3800', and cemented with 5 sacks. Fluid in the hole was bailed down to 300', bridge plug was set on fluid at 300', and 10' of rock bridge, and cemented with 35 sacks. Hole was filled with mud to 40', and 10' of rock bridge, and cemented with 20 sacks to the base of the cellar.

3188' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9/28/64
INV. NO. 9889-W

Signed: Archie Elving
Well Plugging Supervisor