

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSIONJ. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, KansasSEP 24 1964
9-24-64
CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Champlin Oil & Refining CompanyComplete Address: P. O. Box 308, Ellinwood, KansasLease Name Miskimen Well No. # 3Location NW SW SE Sec. 32 Twp. 26 Rge. 12 (E) (W) WCounty Pratt Total Depth 4305Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Ace Pipe Pulling CompanyAddress: Box 304, Great Bend, Kansas License No. 2Operation Completed: Hour 4:30PM Day 23rd Month Sept. Year 1964

The Above well was plugged as follows:

711' of 9 5/8" surface pipe, cemented with 450 sacks. 4304' of 5 1/2" long
string, cemented with 175 sacks. Plug back to 4297'. Top perforation
3670. Plug was pushed to 3650', and cemented with 5 sacks. Fluid level
in the hole was at 315'. Bridge plug was set on fluid at 315', and 10'
of rock bridge, and cemented with 30 sacks. Hole was filled with mud
to 40', and 10' of rock bridge, and cemented with 15 sacks to the base
of the cellar.

3160' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

DATE 9/24/64INV. NO. 9864-WSigned: Archie Elving
Well Plugging Supervisor