

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 3 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Getty Oil Co.

Complete Address: Box 756 Drumright Okla.

Lease Name V.E. Miskimers Well No. 1-A-

Location 4th NE-7W-SW Sec. 32 Twp. 26 Rge. 12 (E) (W) X

County Butt Pratt Total Depth 430.5

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Kerr Well Service

Address: Pratt Kansas License No.

Operation Completed: Hour 6:00 Day 29 Month 8 Year 68

The Above well was plugged as follows:

428 ft 8 5/8 in surface pipe circulated with cement,
430.5 ft 5 1/2 in pipe plugged with 50 sacks cement up to
397.6 ft. Mud and fluid up to 350 ft. A Beershart-Owen
Cast iron plug was expanded there and 2 sacks balmium
Then pipe was perforated to make a fresh water well.
400 ft of 5 1/2 in pipe was recovered.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 9/3/68
INV. NO. 8380-u