

KANSAS

*MP*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

JUN -1 1966

6-1-66  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Anadarko Production Company

Complete Address: P. O. Box 351, Liberal, Kansas

Lease Name McMoran "A" Well No. # 1

Location App. C NW NW Sec. 8 Twp. 35 Rge. 16 (E) (W) W

County Comanche Total Depth 6282'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Bob Sargent Casing Pulling Service

Address: 121 West 9th St., Liberal, Kansas License No. 511

Operation Completed: Hour 12:00 PM May 27th Month May Year 1966

The Above well was plugged as follows:

310' of 13 3/8" surface pipe, cemented with 400 sacks. 5500' of 5 1/2" long  
string, cemented with 170 sacks. Plug back T.D. 5464'. Top perforation  
4930'. 20 sacks of cement was pumped on bottom with the top of the cement  
at 4750', 4222' of 5 1/2" long string was recovered from the hole. At 320'  
5 sacks of Gel-Mud and 50 sacks of cement was pumped in to the 5 1/2" pipe.  
Fluid was bridged at 30', and cemented with 20 sacks to the base of the  
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging Supervisor

DATE 6/1/66

INV. NO. 3315-W