

11-17-87

6030997

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-063-20069-000  
C NE SW, SEC. 12, T 14 S, R 27 W/E

1980 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Sutchiffe Well # AC 3

Operator: Pickrell Drilling Co.

County Gove 138.52

Name & Address 110 North Market Suite 205  
Wichita, Kansas 67202

Well Total Depth 4262 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing Co. License Number

Address Ness City, Kansas

Company to plug at: Hour: PM Day: 17 Month: Nov Year: 19 87

Plugging proposal received from Ed

(company name) Pickrell (phone)

were: 8 5/8" set at 263' w/150 sks. 4 1/2" set at 4326' PBD 4273'

Top perf 3814' 2 stage collar at 1980 w/390sks cwc. Order 150 sks ATL 65/35 Poz 10% Gel  
2% Dixel Cement Blend 5 sks Hulls. Allied Cement Co. Walker Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:10PM Day: 17 Month: Nov Year: 19 87

ACTUAL PLUGGING REPORT

Squeezed 4 1/2" w/150 sks ATL Cement Blend w/5 sks Hulls mixed in.

Max Psi 500#. Close in Psi 200#. Test backside 390# Cement to

surface. Plug complete.

STATE CORPORATION  
DEC 16 1987  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

and observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

DATE 1-7-88

INV. NO. 19409