

4-031899

1-19

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-003 20086-0000

C NE NW /4 SEC. 12, 14 S, 27 W
4620 feet from S section line
3300 feet from E section line

Operator license# 5123

Lease Sutcliffe "AC" well # 2025

Operator: Pickrell Drilling Co., Inc.

County Gove

Address: 110 N. Market
Suite 205
Wichita, Kansas 67202

Well total depth 4390 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 251 feet

142.68

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 19 Month: January Year: 94

Plugging proposal received from: Ed Mondero

Company: Pickrell Drilling Co., Inc. Phone:

Were: Order 350 sxs. 65/35 pozmix - 10% gel - 500# hulls.

STATE RECEIVED
CONSERVATION DIVISION
Wichita, Kansas
FEB - 2 1994
2-2-94

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:00P.M., Day: 19, Month: January, Year: 94

Actual plugging report: 8 5/8" set @ 251' w/140 sxs. cwc. 5 1/2" set @ 4380' w/200 sxs. P.B.T.D. 4343'. D.V. tool at 2017' w/340 sxs. cwc. cement at surface in 8 5/8" - tested - blew out head. Squeezed 5 1/2" with 350 sxs. cement blend with 500# hulls mixed in to Max. P.S.I. 1000#. Close in P.S.I. 1000#. Plug complete.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES 2010 NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 2566 GL

I did (X) / did not observe the plugging.

Carl Goodrow

INVOICED

HO

(agent)

DATE FEB 04 1994

Form CP-2/3

INV. NO. 39854