

To: 1041117  
STATE CORPORATION COMMISSION 10-31  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 151-21,301-00-00  
C SE SW, SEC. 35, T 26 S, R 11 W XX  
660 feet from S section line  
3300 feet from E section line  
Lease Name Huff Well # 1-35  
County Pratt  
Well Total Depth 4530 147.23 feet

TECHNICIAN'S PLUGGING REPORT

Operator License # 31629  
Operator: Nash Oil & Gas, Inc.  
Name: \_\_\_\_\_  
Address 1318 E. 1st  
Pratt, KS 67124

Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 383

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901  
Address: P.O. Box 231, Claflin, KS 67526

Company to plug at: Hour: 8:45 a.m. Day: 31 Month: 10 Year: 19 95  
Plugging proposal received from Kevin Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361  
wore: 4 1/2" at 4347' w/175 sx cement, PBDT 3900', Perfs at 3935.5-37.5, 3872-74'

1st plug sand back to 3820' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 6 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:15 a.m. Day: 31 Month: 10 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 3820' and dumped 4 sx cement on top of sand  
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,  
6 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 800 psi and shut in 400 psi.

NOV - 6 1995

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1890' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
(if desired) observe this plugging.

DATE 11-7-95

Signed Stephen J. Pfeiffer  
(TECHNICIAN)

INV. NO. 43970