

1 090155

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-21,396-00-00

NE NE SW, SEC. 35, T 26 S, R 11 W 24

2310 feet from ~~XX~~S section line

2310 feet from ~~W~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Huff Well # 2-35

Operator: Texas Energies, Inc.

County Pratt

Name & Address P. O. Box 947

Well Total Depth 4500 # 146.25 feet

Pratt, KS 67124

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 390

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A  X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Wheatstate Oilfield Services License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: Noon Day: 20 Month: April Year: 19 84

Plugging proposal received from Larry Belding

(company name) Wheatstate (phone) 316-672-7514

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 4500' with 40 sx cement

2nd plug at 690' with 75 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement

6th plug to circulate mousehole with 10 sx cement. Plug water well with 5 sx cement

Plugging Proposal Received by R. Barburton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None  X

Operations Completed: Hour: 7:15 pm Day: 20 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 4500' with 40 sx cement, 2nd plug at 690' with 75 sx

cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rathole with 15 sx cement, 6th plug to circulate

mousehole with 10 sx cement. Plug water well with 5 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton  
(if additional description is necessary, use BACK of this form.)

INVOICE

(date / did not) observe this plugging.

DATE 4-25-84

Signed R. Barburton  
(TECHNICIAN)

INV. NO. 1265

MAY 03 1984

4-20

FORM CP-2/3  
Rev. 01-84

RECEIVED  
STATE CORPORATION COMMISSION  
APR 24 1984  
CONSERVATION DIVISION  
Wichita, Kansas