

1 031239

8-5

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-22,101-00-00

NW SE SE , SEC. 31 , T 26 S, R 11 W/E

990 feet from S section line

915 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5010

Lease Name Healy Well # 1

Operator: Knighton Oil Company, Inc.

County Pratt

Name & Address 221 S. Broadway, Ste. 710
Wichita, KS 67202

Well Total Depth 4428 143.91 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 254

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling, Inc. License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 7:30 a.m. Day: 5 Month: 8 Year: 19 93

Plugging proposal received from John Armbruster

(company name) Duke Drilling, Inc. (phone) 316-267-1331

work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 630' with 50 sx cement, 2nd plug at 270' with 50 sx cement,

3rd plug at 40-0' with 15 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:30 a.m. Day: 5 Month: 8 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 630' with 50 sx cement,

2nd plug at 270' with 50 sx cement,

3rd plug at 40-0' with 15 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

AUG 10 1993

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

INVOICED

did not observe this plugging.

DATE AUG 18 1993

Signed Steve Durrant (TECHNICIAN)

REV. NO. 38380