

051240

11-29

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,259-00-00
SW NW SE, SEC. 3, T 26 S, R 13 W/E
1650 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Lease Name Chance Well # 1

Operator: Vincent Oil Corporation
Name & Address 125 North Market, Suite 1110
Wichita, KS 67202

County Pratt 137.48
Well Total Depth 4230 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 447

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS

Company to plug at: Hour: 12 p.m. Day: 29 Month: 11 Year: 19 89

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 4195' Perfs at 4132-36' Elevation 1918' GL

1st plug pump 1 sx hulls and 25 sx cement,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 29 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx common cement to 4000',

2nd plug pumped 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 225 psi.

RECEIVED
STATE CORPORATION COMMISSION

DEC - 1 1989

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1897' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED (date) observe this plugging.

Signed Richard M. Lacey
(TECHNICIAN)

DATE 12-7-89

INV. NO. 26698
11-29