

1 040539

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,406-00-00

SE SE SW, SEC. 3, T 26 S, R 13 W/4X

330 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Lease Name Woods Well # A-1

Operator: Pintail Petroleum, Inc.

County Pratt 141.92

Name & Address 412 E. Douglas

Well Total Depth 4367 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well X Gas Well Input Well SMD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 3 p.m. Day: 31 Month: 5 Year: 19 91

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

logs: 4 1/2" at 4363' w/140 sx cement, PBTD 4130', Perfs at 4082-92'

1st plug sand back to 50' above perfs and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 07 1991

Plugging Proposal Received by Steve Pfeifer

(TECHNICIAN)
Wichita, Kansas

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:45 p.m. Day: 31 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4030' and dumped 4 sx cement on top of

sand bridge through bailer.

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2350' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-18-91

INV. NO. 32169

Signed Stephen J. Pfeifer (TECHNICIAN)