

1031547

TO: STATE CORPORATION COMMISSION

API NUMBER 15-151-22,176-00-00
130'W S/2 SE/4 SW/4 SEC. 2, T 26 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1850 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME MEIREIS WELL # 2-14

TECHNICIAN'S PLUGGING REPORT

COUNTY PRATT 142.94

OPERATOR LICENSE # 32154

WELL TOTAL DEPTH 4398 FEET

OPERATOR: SAGEBRUSH OPERATING LLC PRODUCTION CSG: SIZE " FEET

NAME AND 1888 SHERMAN STREET, SUITE 500 SURFACE CASING: SIZE 8 5/8" @ 866' WITH SX

ADDRESS DENVER, CO 80203 CONDUCTOR CSG: SIZE 13 3/8" @ 221'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DUKE DRILLING LICENSE NUMBER 5929

ADDRESS 100 S MAIN, SUITE 410 WICHITA, KS 67202-3737

COMPANY TO PLUG AT: HOUR: 3:00 AM DAY: 07 MONTH: 05 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM JOHN ARMBRUSTER

(COMPANY NAME) DUKE DRILLING (PHONE) 316-267-1331

WERE:

1ST PLUG AT 4340' WITH 40 SX CEMENT. 2ND PLUG AT 800' WITH 50 SX CEMENT.

3RD PLUG AT 240' WITH 30 SX CEMENT. 4TH PLUG AT 40-0' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH

10 SX CEMENT.

 PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 7:00 AM DAY: 07 MONTH: 05 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 4340' WITH 40 SX CEMENT. 2ND PLUG AT 870' WITH 50 SX CEMENT.

3RD PLUG AT 240' WITH 30 SX CEMENT. 4TH PLUG AT 40-0' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH

10 SX CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

MAY 15 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

DUKE DRILLING
SIGNED Steve Durrant
DATE 5/18/00

CONSERVATION DIVISION
Wichita, Kansas
FORM CP-2/3

WV. NO. 621748

(R)